
NOTICE OF INTENT 336 THE TRAIL

PREPARED FOR **ANTHONY RENO** TOWN OF STURBRIDGE WORCESTER COUNTY, MASSACHUSETTS



PLAN SET INDEX

C-1	COVER SHEET
EX-1	EXISTING CONDITIONS PLAN
C-3	SITE PLAN
C-4	SITE DETAILS

TAX MAP REFERENCES: STURBRIDGE ASSESSORS Parcel ID: 640-01435-336

RECORD OWNER: WILLIAM T. LAUGHLIN 32 WALKERIDGE DRIVE NASHUA, NH 03062 DB.32346 PG.121


PLAN REFERENCES:


PLAN BOOK 932 PLAN 100


(WORCESTER COUNTY REGISTRY OF DEEDS)

SITE OVERVIEW SCALE: 1"=100'

NORTH	







FB	PE	
CALISTO J. BERTIN, P.E. OFESSIONAL ENGINEER A. LIC. NO.: 40595 T. LIC. NO.: 12950 I. LIC. NO.: 6694 H. LIC. NO.: 9368	FRANK W BICCHIERI, PROFESSIONAL EN MA. LIC. NO.:	
BRUCE A.	PETER C	

P.E. SITE ADDRESS: ENGLE, P.E.

COVER SHEET NGINEER 336 THE TRAIL
47597 STURBRIDGE, MA 01566




4.03.18 AS NOTED


CLIENT: ANTHONY RENO 14 PRESERVE WAY


STURBRIDGE, MA 01566


39 ELM STREET SOUTHBRIDGE, MA 01550 P 508.765.0195 F 508.765.0193 www.bertinengineering.com 18M-107

32 WALKERIDGE DRIVE NASHUA, NH 03062











DRIVEWAY CROSS SECTION


NOT TO SCALE



THE TOWN ROAD WILL BE SWEPT DAILY WHEN HAULING IS IN PROGRESS. CRUSHED STONE SHALL BE REPLACED WHEN DEPOSITED SOILS ACCUMULATE TO THE EXTENT THAT THEY LESSEN THE EFFECTIVENESS OF THE MAT

STABILIZED CONSTRUCTION ENTRANCE/EXIT





NO. DATE

1" = 50'

SILT FENCE AND STRAW WATTLE DETAIL

NOT TO SCALE

SEQUENCE OF CONSTRUCTION
THE FOLLOWING NARRATIVE DESCRIBES THE PLANNED CONSTRUCTION SEQUENCE WITH AN EMPHASIS ON THE TIMING AND SEQUENCE OF EROSION/SEDIMENTATION CONTROL MEASURES:

THE FOLLOWING CONSTRUCTION SEQUENCE WILL BE REQUIRED TO INSURE THE EFFECTIVENESS OF THE EROSION/SEDIMENT CONTROL MEASURES IS OPTIMIZED.

1. INSTALL STABILIZED CONSTRUCTION EXIT(S) .

2. INSTALL EROSION CONTROL BARRIERS ON THE ENTIRE SITE (CLEAR ONLY THOSE AREAS NECESSARY TO INSTALL SILT FENCE AND

3. CONSERVATION INSPECTION WILL BE CONDUCTED AFTER INSTALLATION OF EROSION CONTROL BARRIERS ARE INSTALLED.
4. TEMPORARILY SEED, THROUGHOUT CONSTRUCTION, DENUDED AREAS THAT WILL BE INACTIVE FOR 15 DAYS OR MORE. PERMANENTLY STABILIZE AREAS TO BE VEGETATED AS THEY ARE COMPLETED.

FINAL PHASE

1. PERMANENTLY STABILIZE ANY REMAINING EXPOSED AREAS.

TEMPORARY DRAINAGE DITCHES TO BE REMOVED AND STABILIZED. 3. ONCE ENTIRE SITE IS STABILIZED, CALL FOR FINAL INSPECTION FROM SITE MONITOR.

NOTES: 1. ONCE CONSTRUCTION IS COMPLETED, ALL DISTURBED AREAS ARE TO BE STABILIZED WITH LOAM AND SEED UNLESS OTHERWISE

2. INSPECTIONS WILL BE CONDUCTED WEEKLY AND AFTER 0.5 INCH RAIN EVENTS. COPIES OF WEEKLY REPORTS AND RAIN EVENT REPORTS SHALL BE SUBMITTED TO THE CONSERVATION COMMISSION WITHIN SEVEN DAYS OF THE INSPECTION.

3. EXTRA EROSION CONTROL MATERIALS (STRAW WATTLES, SILT FENCE) EQUAL TO 100 LF SHALL BE KEPT ON SITE FOR EMERGENCY REPAIRS. THESE MATERIALS SHALL BE KEPT COVERED.

ALL MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON IN ACCORDANCE WITH THE CONTRACT DOCUMENTS OR THE APPLICABLE PERMIT, WHICHEVER IS MORE STRINGENT, AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING:

1. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED,

2. SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED, SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF THE SILT FENCES.

3. THE CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO A PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCE AS CONDITIONS DEMAND.

A. THE STORM WATER POLLUTION PREVENTION PLAN IS COMPRISED OF THIS DRAWING SET ("SITE MAP").

B. CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES (BMP'S) AS REQUIRED. ADDITIONAL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED AS DIRECTED BY CONDITIONS AT NO ADDITIONAL COST TO OWNER THROUGHOUT ALL PHASES OF

C. BMP'S AND CONTROLS SHALL CONFORM TO FEDERAL, STATE OR LOCAL REQUIREMENTS OR MANUAL OF PRACTICE, AS APPLICABLE. CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY PERMITTING AGENCY OR OWNER.

D. SITE MAP MUST CLEARLY DELINEATE ALL STATE WATERS, PERMITS FOR ANY CONSTRUCTION ACTIVITY IMPACTING STATE WATERS OR REGULATED WETLANDS MUST BE MAINTAINED ON SITE AT ALL TIMES.

F. GENERAL CONTRACTOR SHALL DENOTE ON PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA, EMPLOYEE PARKING AREA AND AREA FOR LOCATING PORTABLE FACILITIES,

E. CONTRACTOR SHALL MINIMIZE CLEARING TO THE MAXIMUM EXTENT PRACTICAL OR AS REQUIRED BY THE ORDER OF CONDITIONS.

G. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY

H. SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS SHALL BE MAINTAINED ON SITE OR READILY AVAILABLE TO CONTAIN AND CLEANUP FUEL OR CHEMICAL SPILLS AND LEAKS.

I. DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST

J. RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS; MATERIALS SHALL

BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATER OF THE STATE. K. ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THIS PLAN SHALL BE INITIATED AS SOON AS PRACTICABLE.

L. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 15 DAYS FROM THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS.

M. IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE.

N. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS, OR INTO STORM DRAINS MUST BE

O. CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING SEDIMENTS THAT MAY HAVE COLLECTED WITH THE STABILIZATION OF THE SITE.

P. ON-SITE & OFF-SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BMP'S. STOCKPILE AND BORROW AREA LOCATION SHALL BE NOTED ON THE SITE MAP AND PERMITTED IN

ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS. Q. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION.

R. DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR

ADJUSTING THE EROSION CONTROL MEASURES (SILT FENCES, STRAW BALES, ETC) TO PREVENT EROSION. S. ALL CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY, THIS INCLUDES BACK FILLING OF TRENCHES FOR

UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION. T. NO OVERNIGHT PARKING OF HYDRAULIC EQUIPMENT WILL BE ALLOWED IN THE BUFFER ZONE TO ANY RESOURCE AREA.

U. ANY DISTURBED AREAS OUTSIDE OF THE GROWING SEASON ARE TO BE TREATED WITH WINTER RYE, STRAW MULCH, AND/OR EROSION CONTROL BLANKETS IF ON SLOPES STEEPER THAN 3:1.

ENGINEERING

4.03.18 1"=50'

V. ALL TREE CLEARING DEBRIS SHALL BE REMOVED FROM THE SITE; NO MATERIAL SHALL BE BURIED ON-SITE.

PETER

ENGLE, P.E.

PROFESSIONAL ENGINEER

MA. LIC. NO.: 53736

TITZBACK, P.L.S

PROFESSIONAL

LAND SURVEYOR

MA. LIC. NO.: 37731 CT. LIC. NO.: 16970

LIENT: ANTHONY RENO OWNER: WILLIAM T. LAUGHLIN 14 PRESERVE WAY 32 WALKERIDGE DRIVE NORTH PE STURBRIDGE, MA 01566 NASHUA, NH 03062 EROSION & SEDIMENTATION CONTROL PLAN FRANK W. BERTIN, P.E. BICCHIERI, P.E. SITE ADDRESS: PROFESSIONAL ENGINEER PROFESSIONAL ENGINEER 336 THE TRAIL MA. LIC. NO.: 40595 CT. LIC. NO.: 12950 RI. LIC. NO.: 6694 NH. LIC. NO.: 9368 MA. LIC. NO.: 47597 STURBRIDGE, MA 01566 39 ELM STREET SOUTHBRIDGE, MA 01550 BERTIN

REVISION

18M-107 C-4

www.bertinengineering.com

P 508.765.0195

F 508.765.0193