

VARYING WALL HGT. 1' - 3.5'

100 lb - 4,000 lb boulders

⊙ TELEPHONE

↓
SLOPE DIRECTION

GARAGE

CRUSHED STONE SURFACE

PROPOSE BOULDER RETAINING WALL

EXISTING PAINTED / PRESSURE TREATED WALL TO BE REMOVED

STRAW HAY BALES INSTALLED WHEN
CONSTRUCTION IS NOT UNDERWAY

PROPOSED BOULDER RETAINING WALL

- REMOVE PAINTED PRESSURE TREATED WALL
- REMOVE APPROX. 30 YDS OF EXISTING FILL
- PUSH BOULDER WALL BACK CLOSER TO EXISTING SLOPE
TO REGAIN NATURAL EXISTING SLOPE

DRIVEWAY EDGE

ASPHALT PARKING

← ENTRY DRIVEWAY →

DRIVEWAY EDGE

STRAW WATTLE

SILT FENCE

⊙ EXISTING TREE

SHORE LINE

43'

26'

46'

56'

CEDAR LAKE

FLOATING HYDRAULIC DOCK
← 100' →

McCONNELL RESIDENCE

SCALE: 1/4" = 1'

APPROVED BY:

DRAWN BY

DATE: 9/18/18

REVISED

34 CEDAR LAKE DR.

BOULDER WALL PROPOSAL

DRAWING NUMBER