

NORMAL LOW WATER



WETLAND PROTECTION MEASURES:

1) STAKED STRAW WATTLES SHALL BE INSTALLED AS SHOWN ON THE PLAN. THEY SHALL BE INSPECTED BY THE LOCAL CONSERVATION COMMISSION, IF REQUIRED, BEFORE CONSTRUCTION.
2) WITHIN THE 100ft BUFFER ZONE ALL DISTURBING OF SOIL SHALL BE MINIMIZED.
3) ALL DISTURBED AREAS SHALL BE LOAMED. SEEDED AND MULCHED AS SOON A POSSIBLE.
4) NO WORK OR STORAGE OF MATERIAL SHALL BE DOWN HILL OF THE STRAW WATTLES.
6) ALL NECESSARY PERMITS SHALL BE OBTAINED BEFORE WORK COMMENCES.
7) OWNER AND CONTRACTOR SHALL ADHERE TO ANY ORDERS ISSUED BY THE LOCAL CONSERVATION COMMISSION.

LEGEND




THE ELEVATION FOR THIS PLAN IS SET TO THE NAVD88 DATUM.

THIS ELEVATION WAS ESTABLISHED UTILIZING A CHC X-90 OPUS DUAL CHANNEL GPS RECEIVER.

DATA WAS COLLECTED FOR A 15 MINUTE PLUS PERIOD AND SUBMITTED TO THE NATIONAL GEODETIC SURVEY OPUS SITE FOR POST PROCESSING.

LOCUS MAP





THE PURPOSE AND INTENT OF THIS PLAN IS TO PERMIT THE LAKE FRONT SITE IMPROVEMENTS AS SHOWN ON THE PLAN

THE EXISTING CONDITIONS ON THE SITE INCLUDE WOODEN RETAINING WALLS THAT ARE SEVERELY COMPROMISED AND ARE AT RISK OF COLLAPSING INTO THE LAKE.

THE PROPOSED NATURAL STONE WALL WILL PROTECT THE SHOREFRONT AND WILL RESULT IN A NET REDUCTION OF FILL BELOW THE 100 YEAR FLOOD ELEVATION.

ALL IMPROVEMENTS WILL ALLOW THE INFILTRATION OF RAIN WATER AND RE-VEGETATE THE SLOPE TO PROTECT IT FROM EROSION.



10 MAIN STREET STURBRIDGE, MA 01566 508-347-5226 (W) 508-347-9857 (F)

WORKING TO PROTECT OUR WATER RESOURCES

PERC TESTING SEPTIC DESIGN WETLAND PERMITTING ENVIRONMENTAL CONSULTING

PROPOSED SITE IMPROVEMENTS

SHORE RESTORATION

ANDREW & MARIEL HOULE

64 SOUTH SHORE DRIVE

STURBRIDGE MA

7 JUNE 2018

MAP 6 PARCEL 64

PLOT: 6/28/2018 6:17 AM SHEET 1 OF 1 JOB: 2016—152